

INSPECTION REQUIREMENTS FOR POOLS

INGROUND POOLS

1. Footing – **AFTER** concrete collar is poured as per manufacturer specifications.
2. Pool Steel – **PRIOR** to placement of concrete or gunite.
3. Electrical - **BONDING**.
4. Electrical - **PIPE** and **TRENCH**.
5. Plumbing - **PIPE, TRENCH** and **AIR TEST**. (Pool Heater if applicable)
6. Final Electric
7. Final Plumbing (If applicable)
8. Final Fire (If Applicable, pool heater located inside a structure)
9. Final Building – *All permanent fencing and/or barriers need to be installed in order to have final inspection.*

ABOVE GROUND POOLS

1. Electrical **ROUGH, BONDING, or TRENCH**. (*Do not energize or seal any equipment until inspection passes*)
2. Plumbing - **PIPE, TRENCH** and **AIR TEST**. (Pool Heater if applicable)
3. Final Electrical
4. Final Plumbing (If applicable)
5. Final Fire (If Applicable, pool heater located inside a structure)
6. Final Building – *All permanent fencing and/or barriers need to be installed in order to have final inspection.*

(Other inspections may be required depending on the scope of the project. Consult the Subcode Official if you have any questions.)

Inspection Requests: For Inspections call Cheryl between the hours of 8:30am to 4:30pm, Monday thru Friday.

You must have the following information in order to request an inspection. (PERMIT #, BLOCK/LOT, NAME & ADDRESS AND TYPE OF INSPECTION) Provide any other information that may be needed.

**ONLY CALL FOR INSPECTIONS WHEN THE WORK IS READY. DO NOT ANTICIPATE!!
N.J.A.C. 5:23-2.18 (c) 1.**

If your inspection is not approved, do not call for re-inspection until the problems are repaired and the work is ready for re-inspection.

If your inspection is not approved a second time for the same violation you will receive a penalty notice. Your next re-inspection will be 3 business days after your next request.